

CURVE	LENGTH	RADIUS	DELTA	TANGENT	CHORD	CHORD BEARING
C1	120.02'	1118.00'	6'09"03"	60.07'	119.96'	N24°04'09"E
C2	236.13'	995.00'	13'35"51"	118.62'	235.58'	S19°46'02"E

MAP SYMBOL	SOIL NAME	SOIL GROUP	NATURAL SOIL GROUP	HYDRAULIC SOIL GROUP	DWELLINGS TWO STYS OR LESS	STREETS AND PARKING LOTS	SWELL POTENTIAL	FACTOR
AVe	AURA & CROOM GRAVELLY LOAMS	20-50%	B2c	B	MOD. TO SEVERE	SEVERE	LOW	0.43
SHB2	SASSAFRAS SANDY LOAM	2-5%	B1a	D	SLIGHT	SLIGHT	LOW	0.32
BB2	BELTSVILLE SILT LOAM	2-5%	E2a	C	MODERATE	MODERATE	LOW	0.43

NOTES:

- A HYDRANT WILL BE USED FOR WASH WATER.
- SEE EROSION AND SEDIMENT CONTROL NOTES SHEETS FOR EROSION AND SEDIMENT CONTROL DETAILS AND NOTES.

Figure 2 Temporary Sediment Basin Design Data Sheet

Computed by: RW Date: 4/06/07 Checked by: RW Date: 4/06/07

Project name: BETH SHALOM AME ZION CHURCH Basin #1

Location: RITCHIE ROAD, SOUTH OF D'ARCY ROAD, DISTRICT HEIGHTS, MD.

Total area draining to basin: 1.32 acres (ac)

Basin Volume Design

Note: 1. Also see Surface Area Design #30, this form.
2. To convert ft³ to yd³, divide ft³ by 27. To convert ft² to yd², divide ft² by 9.

- Min. required vol. = 3600 ft³/ac x 1.32 ac. drainage = 4,752 ft³
- Actual Volume of basin = 13,308 ft³
- Excavate 13,308 ft³ (493 yd³) to obtain required capacity.
- Vol. at dewatering elev. = 1800 ft³/ac x 1.32 ac. = 2,376 ft³
- Vol. of basin at cleanout = 900 ft³/ac x 1.32 ac. = 1,188 ft³
- Elevation corresponding to min. required volume of basin (riser crest elevation) = 251.75 ft.
- Permanent pool elevation = 250.88 ft.
- Distance from riser crest elevation to permanent pool elevation = 0.87 ft.
- Basin cleanout elevation = 250.44 ft.
- Distance from riser crest elevation to cleanout elevation = 1.31 ft.

Spillway Design

- Q₁₀ = 11 cfs (peak discharge from 10-yr, 24-hr storm event, attach computations) SEE COMPUTATION SHEETS ACCOMPANYING PLANS
- Design Principal Spillway (Barrel) discharge, Design Q₁₀ = 11 cfs (min. 10% of 10 year peak or 8" Diameter Pipe)
- H = 3.0 ft.; Barrel length = 42 ft.
- Barrel Diam. 18 in. Note: Q₁₀ must equal or exceed Design Q₁₀. Q₁₀ = Q (from Table 13 or 14) 13.6 x (length correction factor) 1.10 = 15.0 cfs.
- Riser Diameter 48 in.; Riser Height 3 ft.; Riser Head (h) = 0.54 ft.
- Trash Rack Diam. 72 in.; Trash Rack Height = 21 in.

Principal Spillway (Cont.) (See Detail 11)

- Design Principal Spillway (Barrel) discharge, Design Q₁₀ = 11 cfs (min. 10% of 10 year peak or 8" Diameter Pipe)
- H = 3.0 ft.; Barrel length = 42 ft.
- Barrel Diam. 18 in. Note: Q₁₀ must equal or exceed Design Q₁₀. Q₁₀ = Q (from Table 13 or 14) 13.6 x (length correction factor) 1.10 = 15.0 cfs.
- Riser Diameter 48 in.; Riser Height 3 ft.; Riser Head (h) = 0.54 ft.
- Trash Rack Diam. 72 in.; Trash Rack Height = 21 in.

NOTE: A table showing design data shall be included on the plan for each basin.

Emergency Spillway (Optional)

THE PRINCIPAL SPILLWAY WILL BE USED AS THE EMERGENCY SPILLWAY

- Emergency spillway cap., Q₁₀ = Q₁₀ - Q₁ = _____ cfs
- Width _____ ft.; Hp _____ ft.
- Entrance channel slope _____ %.
- Exit channel slope _____ %.

Anti-Seep Collar Design (If Required)

- y = 3 ft.; z = 2 ft.; pipe slope = 1.83 %; L_s = 20 ft.
- Use 1 collars, 5 ft. - 6 in. square; projection = 2 ft.

Design Elevations



- Riser Crest = 251.75 ft.
- Design High Water = 252.29 ft.
- Emergency Spillway Crest = 251.75 ft.
- Min. settled top of dam = 254.00 ft.
- Permanent pool = 250.88 ft.
- Bottom of Basin = 250.00 ft.
- Draw-down orifice invert = 250.88 ft.

Surface Area Design

- Min. basin surface area; SA ≥ 0.0035 x Q₁₀ = 0.0035 x 11 cfs = 0.0385 ac. (BASIN AREA AT 254 CONTOUR = 4,619 S.F. OR 0.106 AC.)

Draw-down Device

- Draw-down device orifice diameter = 4 in. (From Table 11)
- A₁ = Total area of perforations ≥ 4A₂
A₁ = (# of perforation/foot)(perforation area ft²)(perforated section length ft.)
A₁ = 0.348 ft² 4(0.087) = 0.348
A₂ = Internal orifice area (from Table 11 or computed) 0.087 SF MAX. PER TABLE 11



EROSION AND SEDIMENT CONTROL LEGEND

KEY	SYMBOL	DESCRIPTION
CE	[Symbol]	CONSTRUCTION ENTRANCE
SSF	[Symbol]	SUPER SILT FENCE
OP	[Symbol]	ROCK OUTLET PROTECTION
SIP	[Symbol]	STORM DRAIN INLET PROTECTION
TP	[Symbol]	TREE PROTECTION
SP	[Symbol]	SUMP PIT
[Symbol]	[Symbol]	DIVERSION DIKE
[Symbol]	[Symbol]	DRAINAGE DIVIDES
[Symbol]	[Symbol]	LIMITS OF CLEARING & GRADING
[Symbol]	[Symbol]	CRITICAL SLOPE AREA (15% - 33%)

CRITICAL SLOPES SHALL BE SEEDED, MULCHED AND TACKED WITHIN 14 DAYS AFTER START OF GRADING, OR SODED AND PEGGED WITHIN 14 DAYS AFTER START OF GRADING.

CAUTION - NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS AND TO VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

REVISIONS:

WARDER
Your Church Builder
Phone: (301) 868-5900
Toll Free: (800) 732-7266
Fax: (301) 868-8740
www.wardergroup.com

WE Inc.
Williams Enterprises Incorporated
18 Mosby Lane Stafford, Virginia 22556
540-286-3710 and 540-286-0345 Fax
weinc@hughes.net

PROFESSIONAL ENGINEER
5/26/07

DATE: APRIL 2007
SCALE: 1"=30'
DRAWING NAME: 19D09-ES

GRADING & EROSION & SEDIMENT CONTROL PHASE I

PROJECT: **BETH SHALOM AME ZION CHURCH**
6TH ELECTION DISTRICT
PRINCE GEORGE'S COUNTY, MARYLAND

SHEET SC 2 OF 7
FILE No. MDPG-19D09-01